

Criscuolo Engineering, LLC

Consulting Engineers
Civil Engineers
Land Surveyors

Robert A. Criscuolo, P.E., L.S.
Paul L. Nott, L.S.
James M. Pretti, Jr., P.E.
Linda C. Dow, P.E.

Records of:

Associated Surveys
Charles H. Miller
George A. Firth

MEMORANDUM

To: Greater New Haven Water Pollution Control Authority
From: James M. Pretti, Jr., P.E.
Date: 2/20/2020
Re: James Street Siphon Chamber Upgrades Project – Addendum #2
CE File No: 2017.097
cc: file

In regards to questions set forth in email from Kovacs Construction Corporation dated 2/14/2020, we have the following responses:

1. a. Only the new electrical room and re-fitted bathroom need to be painted.
b. 1. The bathroom will have one wall mounted toilet, one wall mounted urinal and one wall mounted sink. No new partitions.
2. Provide one toilet paper dispenser and one paper towel holder. Both surface mounted.
3. The hot water heater should be mounted on the wall near the new sink in the bathroom.
4. Remove the tiles. The CMU walls and concrete floor shall be stripped to the concrete and repainted. The sheetrock wall shall be replaced and painted.
c. The panel above the door to be in-filled for the generator louver shall be filled in with masonry as well.
2. a. The allowance for the testing is in the schedule of bid items.

Additional information:

1. An attempt has been made to operate the existing slide gates with no success. Contractor will need to sandbag and build a cofferdam to isolate either channel.

420 East Main Street, Building 1, Suite 9, Branford, CT 06405
Phone (203) 481-0807 Fax (203) 488-5729 e-mail: office@cengineeringllc.com